

# Illustrated Parts List - IPL Update



Product Name(s)

**H 3120 XP**

Description of change

1. Ignition Module 503 13 85-01 (cut-out 11000 rpm) removed and replaced by Ignition Module Assy (Kit) 595 31 26-01  
Reason: If a module 503 13 85-01 (chainsaw up to s/n 20172700017) fails you must change both Ignition module and flywheel, therefore we have a new Kit 595 31 26-01 containing Ignition Module 587 32 94-01 (cut-out 9800 rpm) and Flywheel 522 89 20-02.
2. Ignition Module 544 01 88-01 replaced by 587 32 94-01, supplier change.

Comments

587 32 94-01 not interchangeable with 503 13 85-01  
587 32 94-01 fully interchangeable with 544 01 88-01


Introduced from

Serial number / Date	Remark
20172700017	Ignition Module 587 32 94-01


IPL updates

Page Title	Ref. no	New part no	Name	Excl. part no.	Remark
Ignition System	7	587 32 94-01	Ignition Module	503 13 85-01*	*(cut-out 11000 rpm)
Ignition System	7	587 32 94-01	Ignition Module	544 01 88-01	(cut-out 9800 rpm)
Ignition System	17	595 31 26-01	Ignition Module Assy		(cut-out 9800 rpm)

## Ignition Module Assy




595 31 26-01




Old  
503 13 85-01

# Illustrated Parts List - IPL Update



587 32 94-01



544 01 88-01